

SCHEDULE A – TANK REPLACEMENT (Tank N-2A-07) (BASE BID)

	DESCRIPTION	Qty	UOM	UNIT PRICE \$ (Word and Figure Amount)	TOTAL COST\$ (Figure Amount)
1	Mobilization/Demobilization, Bonds, permitting and Insurance	1	LS		\$
2	Demolition of Existing Tank and Retaining Ring	1	LS		\$
3	Tank Concrete Ring Foundation	120	CY		
4	6" Oil Impregnated Sand Base	190	CY		
5	16" Inlet/Outlet Piping	40	LF		
6	16" Interconnecting Piping	30	LF		
7	16" Overflow Pipe	25	LF		
8	Hydrostatic Testing and Disinfection	1	LS		
9	Site Grading	1	LS		
10	Chain-link Fence Installation	150	LF		
11	Cathodic Protection System for Welded Steel Tank	1	LS		
12	1.5 MG Welded Steel Tank with Aluminum geodesic dome Roof (anodized finish or PVDF powder coating finish)	1	LS		
13	Tank Interior and Exterior Coatings	30,000	SF		
14	Tank Electrical, Instrumentation and Controls	1	LS		
15	Tank inspections	1	LS		
16	Force Account	1	LS	\$50,000 (Fifty Thousand Dollars)	\$50,000
Total Schedule A					

The quantities specified are to be considered approximate quantities only. A price is to be provided in order to establish a unit cost for extra work directed by the Engineer in the event that unforeseen conditions are encountered. Payment for the actual quantity furnished, installed, or constructed as described in Unit Price Item(s) will be made at the unit price set forth above provided the actual quantity furnished, installed, or constructed are supplied. The City reserves the right to complete all, none or an adjusted quantity of Work under this Bid Schedule.