



LAKE HAVASU CITY, ARIZONA

ADDENDUM NO. 1

City Core Pavement Rehabilitation

Project No: PW23-106012-500325

Dated: October 13, 2023

This addendum forms a part of the contract described above. The original documents in full force and effect are modified by the following changes. Addendum No. 1 will take precedence over any conflicting provision in the prior documents.

Each bidder shall acknowledge receipt of this addendum and by affixing its signature on the acknowledgement form attached, by noting this addendum on the Bid Form and by attaching this Addendum and/or acknowledgement to its bid.

The following changes are to be made and become part of the Bid/Contract Documents. The changes are as follows:

- 1) Please find the enclosed non-mandatory pre-bid agenda, sign in sheet and contractors questions with written responses prepared by the city.

By:

Mike Wolfe, P.E.



Date: 10/13/2023



City Core Pavement Rehabilitation
Non-Mandatory Pre-Bid Meeting Agenda
Wednesday, October 11, 2023 @ 2:00 pm

- 1.) Round table introduction and Sign-In Sheet.
- 2.) Project Plans and Specifications are available on City website and www.DemandStar.com.
- 3.) Deadline for questions is October 18, 2023 at 3:00 pm
- 4.) The scope of work includes, in general terms, the following:

This project consists of the mill and overlay of McCulloch Blvd. between the London Bridge Road and Smoketree Ave, Swanson Ave. between US 95 and Smoketree Ave, Smoketree Ave. between Swanson Ave and Mesquite Ave, and Riviera Blvd. between Swanson Ave. and Palo Verde South. Water main replacement is also included within Swanson Ave between Magnolia Dr. and Capri Blvd. and Riviera Blvd. between Swanson Ave. and Palo Verde South. The water main replacement consists of replacing of the existing main existing hydrants and services will be maintained and reconnected to the new main.

- 5.) Preparation and Submission of Bids:
 - a. Found in section 00300.
- 6.) Contract Time:
 - a. There are **180 Calendar days** allotted for the completion of the project.
 - b. Bid Opening Date: October 25, 2023
 - c. Anticipated Award Date: November 14, 2023
 - d. Anticipated Contract Signing Date: November 21, 2023
 - e. Anticipated Issuing NTP: Jan 2, 2024
 - f. Anticipated Completion date: June 30, 2024
- 7.) General questions?



Questions Received Via Procurement

Item No1:

On page WT02 at the first tee specs out a 8"x4" tee but then asks to connect a 6" line to that 8" x 4" tee. I assume you want a 4" line as it's connecting to an existing 4" line.

In regards to sheet WT02, The water line lateral located at Station 212+56.77 should consist of 4" PVC C900 DR 14. The 8"x4" tee called out is correct. Please remove Water Note 15 from station 212+56.77.