



LAKE HAVASU CITY
Administrative Services

PROCUREMENT DIVISION

INVITATION TO BID
Dick Samp Pickleball Court Improvements
PROJECT NO. PK1140
ADDENDUM NO. 1
07/27/20

Attention is called to the following changes, additions, clarifications and/or deletions to the original solicitation and they shall be taken into account in preparing submissions:

There is no change in the opening date. **Submissions are due no later than 3:00 p.m., Arizona Time, August 5th, 2020** at the City Clerk's Office, 2330 McCulloch Blvd. N., Lake Havasu City, AZ 86403.

ITEM	ACTION	DESCRIPTION or ISSUE
1	Clarification	Q: There appear to be no electrical drawings. Please advise. A: The City intends to make the electrical improvement as part of a later phase. That is why it is a general lump sum. It will be conduits & pull-boxes only in this contract.
2	Amendment	Q: The drawings have nothing indicating size of wire or conduit required for the lighting and fiber. There seems to be no indication of the location of the power source for the lighting. Please advise. A: The conduit runs depicted in the plans should be 2". This results in an addition of 1700 LF of 2" conduit and 13 EA, L-25" x W-16" x H-12" Concrete Pull Boxes. These should be added as incidental items to Item 41 – Pickleball Lighting Footers & Associated Conduit
3	Clarification	Q: We ask that you consider Hellas' surfacing product and Hellas as an approved manufacturer and installer of our TPS™ 5000 acrylic surfacing system as equal to the currently specified product. A: The City is unable to verify the durability of this product as the provided contact numbers for previous project owners in similar climates were erroneous, or in the case of the public schools, unavailable for comment until too late in the advertising process to properly evaluate.
4	Clarification	Q: Will structural drawings be available prior to August 5th? If not, should we proceed with pricing the post tension slabs based on assumptions. A: The final shop drawings will need to be provided as a submittal. This was intended to facilitate coordination of tendon layout vs post layout in the field. The appurtenant construction notes and details can be located on C4 & C5 of the planset and in section 027700 of the Specifications.

5	Clarification	<p>Q: • Refer to drawing L-2, it is referencing Apache brown 1/2" mulch. This is not available. There is an apache gold 5/8" minus DG and a saddleback brown 1/2" minus. There is also a 1/2" screened Aztec Gold. Is it the intent to match the existing DG? It appears that this is a desert red 3/8" minus that appears to be available. Please confirm.</p> <p>Q: • Refer to drawing L-2 that is referencing Apace brown 4" -8" Riprap. There is not an apache brown available. There is an apache gold but only available in 1" to 4". Please confirm if this is acceptable. Also, there is a 4" to 8" Aztec gold available. Please confirm if this would be acceptable. It would match the color of the 1/2" screened Aztec Gold DG if that was selected. A: The City will go through a submittal process where you can present samples (5 gallon bucket) for consideration. We will allow alternatively named colors as long as the intent is achieved.</p>
6	Clarification	<p>Q: Can vapor barrier and saw cutting be eliminated based on the post tension engineers recommendation? A: No to both. The City is building on top of a closed junkyard so the vapor barrier will be necessary. The sawcutting will be necessary. The minimum cut depth is 3/4" and the tendons have a minimum of 2" of concrete cover.</p>

DATE: 7/27/2020BY: Lynette Singleton
Lynette Singleton, Procurement Official