

SECTION 01520

FIELD OFFICES AND SHEDS

PART 1 - GENERAL

1.1 SUMMARY

A. This Section includes requirements for temporary field offices and other structures required for office and storage space required by Contractor.

B. Related Work Specified Elsewhere

Equipment and MaterialsSection 01600
Temporary Utilities and FacilitiesSection 01560

PART 2 - PRODUCTS

2.1 Field Offices

A. General

1. Provide trailers, mobile buildings, or buildings constructed with floors raised aboveground, with steps, landings, and railings at entrance doors.
2. Buildings shall be structurally sound, secure, and weathertight.
3. Provide appropriate type fire extinguishers at each office and storage area.
4. Maintain offices during progress of the Work.
5. Install office spaces ready for occupancy 15 days after date stated in Notice to Proceed.

B. Contractor's Office

1. Provide a field office for Contractor's superintendent on the Site.

2. It shall be of size required for general use, with lights, heat, air, furnishings, telephone service, and other necessary facilities and utilities required by Contractor's operations.

2.2 Storage Sheds and Trailers

A. On Site

1. Provide temporary buildings or trailers needed for storage of Equipment and Materials installed under this Contract (and those furnished by Owner or others under separate contract).
2. Provide ventilation, heating and placards as required by Equipment and Material stored.

B. Off Site

1. Advise Engineer of any arrangements made for storage of Equipment and Materials in a place other than Owner's Site. Furnish evidence of insurance coverage with Application for Payment in conformance with the GENERAL CONDITIONS.

PART 3 - EXECUTION

3.1 Location, Installation and Maintenance

A. General

1. Place temporary buildings, trailers, and stored materials in locations acceptable to Owner or Engineer.
2. Install field offices and sheds to resist winds and elements of the locality where installed.
3. Remove when no longer needed at the Site or when Work is completed.
4. Keep approach walks free of leaves, mud, water, ice, or snow.
5. At completion of Work, remove temporary buildings and trailers, foundations (if any), utility services, and debris.

6. Prepare ground or paved areas as specified in applicable Sections.

PART 4 - MEASUREMENT AND PAYMENT - Not Applicable

**** END OF SECTION 01520 ****